



3.3 Attic Vents and Covers (Hurricane Designation Only)

Ridge and off-ridge vents must be TAS 100(A) rated and anchored to the roof in compliance with manufacturer recommended installation for high winds.

Gable end vents must have removable shutters in accordance with FORTIFIED Standard Detail **F-GS-1** "Gable Vent Shuttering" (refer to Appendix A), and homeowner must be made aware that installation of shutters is temporary and that shutters must be removed once the hurricane threat has passed.




Figure 3.2. Example of a gable end vent



Figure 3.3. Outside shuttering of a gable end vent with Plywood



Figure 3.4. Shuttering of gable end vent from inside attic



F-GS-1